

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

1-16-14
Plotted
W. S. J.


SHELL PETROLEUM CORP.
J. J. Stettinger No. 6.

SEC. 1 T. 16 R. 14W.
SE SW SE
330' SL 988' WL. SE $\frac{1}{4}$

Total Depth. 3343
Comm. 10-23-38 Comp. 11-27-38.
Shot or Treated. 2000 gal.
Contractor.
Issued. 1-14-39

County Barton.

1939



CASING.

8 5/8" 668'
4 1/2" 3324'

Elevation.

Production. Pot. 2485 B.
No wtr.

Figures Indicate Bottom of Formations.

surface soil	20	lime	3040
shale and shells	55	lime	3128
shale	57	shale and lime	3136
sand	65	limo	3179
shale and lime	214	lime	3278
shale and lime	306	broken limo	3287
shale	350	lime	3321
shy shale with lime	410	dolomite grey to grey	
shale & lime strks	430	brown small amt wh	
shale	445	chert	3323
shale & lime	573	dolomite light grey to	
shale	646	brown grey	3325
sand and shale	655	3325 equals 3327 S.L.C.	
shale	668	Dolomite	3343
red bed	870		
anhydrite	900	Total Depth.	
shale and lime	992		
shale & lime strks	1116	Thin strks fair porosity with fair oil stain	
shale and shells	1205	and small amount of good stain 2976-94	
broken lime	1223		
shale and lime	1330	fair porosity with trace of light oil	
shale	1410	stain 3108-12	
salt and shale	1528		
shale and anhyd.	1545	fair to good porosity with trace of	
anhydrite	1560	oil staining. 3128-46	
anhydrite & shale			
streaks	1606	good porosity, no oil stain 3189-3200	
lime	1661		
anhydrite	1685	fair to good porosity with trace oil stain 3237-44	
lime and shale	1742		
lime and shale	1815	fair porosity and oil stain. 3318-23	
shale	1834		
lime and shale	1873	poor porosity and small amount oil staining 3321-3323	
broken lime	1885		
lime	1927	Top Arbuckle Dolomite 3325.	
lime and shale	1969		
broken lime	2031	small amount porosity with occasional good oil	
lime	2082	staining 3323-3325	
lime and shale	2130		
lime broken	2167	No oil showing in bailer at 3327	
lime & shale strks	2215	1600' oil at 3333	
lime and shale	2256	2730' oil at 2:05 AM	
broken lime and		2825' oil at 2:30 AM	
shale	2321	2880' oil at 5 AM 3333	
limo	2355		
shale and lime	2458	swab 63 oil and no water 4 hours, swabbing from	
lime and shale	2758	2900' to 1300' off bottom.	
shale	2801		
lime	2815	Est. Pot. of 2485 B., and no wtr, pumping 828.38 B.	
lime	2836	in 8 hours.	
lime and shale	2913		
limo and shale	3002		