

2-16-14 w

Company- SHELL OIL CO.

Farm- G. Batt "B"

No. 6

SEC. 2 T. 16 R. 14W
CN/2 NW SE

330' fr NL 660' fr WL

Total Depth. 3366 PB 3316

Comm. 6-25-52

Comp. 7-11-52


Shot or Treated.

Contractor.

Issued. 8-30-52

County Barton

KANSAS



CASING:

8 5/8" 630'

4 1/2" 3350'

Elevation. 1863

Production. Pmp. 26 BO & 1 BW
24 hrs.

Figures Indicate Bottom of Formations.

surface clays, post
 rock & shale 270
 shale & shells 590
 shale & pyrite strk 636
 anhydrite 912
 shale & shells 1590
 shale & lime strks 1635
 lime 2185
 lime & shale 2300
 lime 2340
 shale 2362
 lime 2370
 shale 2393
 lime 2444
 shale 2454
 sand 2460
 shale 2463
 sand 2484
 shale 2502
 lime 2512
 dolomite 2520
 shale & dolomite 2528
 shale & sand 2566
 lime 2606
 shale 2612
 lime 2625
 shale 2634
 lime 2650
 shale 2668
 lime 2674
 shale & lime 2682
 shale 2702
 lime 2727
 shale 2735
 lime 2752
 shale 2775
 lime 2857
 shale blk 2861
 lime 2876
 shale 2881
 lime 3003
 shale & bks carbon-
 aceous 3007
 shale & lime 3017
 lime 3034
 shale 3068
 lime 3079
 shale 3084
 lime 3135
 shale 3145
 lime 3150
 shale 3154
 lime 3212
 shale 3219
 lime 3274
 shale 3281
 lime 3303
 conglomerate 3366
 Total Depth PB 3316

Tops:
 Tarkio 2502
 Topeka 2775
 Heebner 3003
 Toronto 3017
 Brown Lime 3068
 Lansing-K. C. 3084
 Sooy 3303

Perforated 40 shots 3293-3303'
 2,000 gals. acid 3293-3303'