

2-16-14w


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SHELL OIL CO.
Farm. P. Schneider "C" No. 8

SEC. 2 T. 16 R. 14W
NE SE NE
1090' fr SL 330' fr EL

Total Depth. 3353 P.B.T.D. 3313
Comm. 10-16-52 Comp. 11-5-52
Shot or Treated. Perf. 40/3284-94
Contractor.
Issued. 2-28-53

County Barton
KANSAS



CASING:
10 3/4 629'
7 in. 3352'

Elevation. 1866

Production. Pump 37 BO 171 BW

Figures Indicate Bottom of Formations.

surface soil, sand & red rock	40
sand & red rock	100
brown lime & shale	300
shale & sand	400
shale & shells	460
sand & shale	500
shale & shells	649
red bed & shale	840
red bed	845
anhydrite	872
shale & shells	1540
lime, shale & shells	1600
lime & shale	2195
shale & shells	2300
shale & lime	2315
lime & shale streaks	2340
lime & shale	2380
lime & some shale	2438
sand & shale streaks	2460
shale & sandy shale streaks	2490
lime	2507
shale & sand streaks	2551
lime & shale streaks	2610
shale, sandy lime streaks	2621
lime & shale streaks	2631
shale & sand streaks	2663
shale	2680
lime & shale streaks	2740
shale	2761
lime & shale streaks	2938
lime	2990
shale	2994
lime & shale	3006
lime	3021
shale & lime streaks	3056
brown lime	3067
shale	3072
lime	3090
shale	3095
lime	3133
lime & shale	3150
lime	3197
lime & shale	3205
lime, considerable shale	3214
lime & shale streaks	3222
lime	3228
lime & shale streaks	3243
lime	3258
lime & shale	3270
lime	3277
lime & shale	3284
dolomite	3353
Total Depth	P.B. 3313

TOPS:
Tarkio 2490
Topeka 2761
Heebner 2990
Toronto 3006
Brown lime 3056
Lansing KC 3072
Arbuckle 3284
Perf. 40/3284-94