

3-16-14w


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STERLING DRILLING CO. ET AL
Farm- Popp No. 1

SEC. 3 T. 16 R. 14W
SW SW NE

Total Depth. 3357'
Comm. 9-27-58 Comp. 10-18-58
Shot or Treated.
Contractor. Sterling Drlg.
Issued. 1-31-59

County Barton
KANSAS



CASING:

8 5/8" 240' cem w/150 sx.
5 1/2" 3352' cem w/75 sx.

Elevation. 1904'

D.V. Tool @ 907' w/200 sx Pozmix w/2% gel added,
200 sx regular Pozmix. Figures indicate Bottom of Formations.

Production. 11 BOPD

shale & shells	240
shale, red bed & sand	540
red bed	895
Anhydrite	925
red bed & shale	1240
shale & salt	1575
shale & lime	1810
lime	2050
shale	2175
shale & lime	2370
shale	2650
shale & lime	2765
lime	2940
lime & shale	3020
lime	3070
lime & shale	3160
lime	3335
shale	3357 RTD
Total Depth	

TOPS: SCOUT

Heebner	3051
Douglas	3032
Brown Lime	3110
Lansing	3133
Arbuckle	3350