

Dawn C. Dunn #1

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

26-32-2E
SW SE SW

Elev. 1187' RB


DUNN #1

SW SE SW Section 26-32S-2E
Sumner County, Kansas

Commenced: September 24, 1969
Completed: October 8, 1969

OPERATOR - Derrick-American Oil Inc.

PMP 44BOPD450
Miss.
GR 39.8



DEPTH	FORMATION	REMARKS
From To		
0 60	Surface clay and sand	Ran 6 joints of 8-5/8" casing, set @ 133' w/135 sacks cement.
60 2246	Shale and lime	
2246 2260	Stalnaker Sand	Ran 111 joints of 4-1/2" casing, set @ 3604', 1' off bottom, w/175 sacks cement. Halliburton guide shoe and insert float cemented @ 3335', 3254' and 3170'.
2260 2644	Lime and shale	
2644 3311	Lime	
3311 3340	Kinderhook Shale	
3340 3530	Lime and shale	
3530 3605 3605	Lime	
3605 TD		

I, JAMES S. SUTTON II, certify this is a correct copy of the Drillers' Log for the well drilled in the SW SE SW Section 26-32S-2E, Sumner County, Kansas, to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 17 day of October, 1969, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act, and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

Log Taps



Latan	2156
Stalnakel	2202
U. Layton	2584
L " "	2642
Kansas city	2660
Mississippi	3116
Simpson	3501
Orbuckle	3585

