

Top 285 Page 165
location NW 1/4 NW 1/4
Wilson Co - Kansas
Elevation - 1080'

State Geological Survey
WICHITA BRANCH
Commenced 10/23/80
Completed 10/25/80

SEP

PS

DRILLER'S LOG

HAROLD OLSON #1
DATE - 10/27/80

14-28-16E

3	Soil	3
5	Clay	8
113	Shale	121
9	Lime	130
93	Shale	223
6	Lime Shaley	229
7	Lime	236
42	Shale	278
10	Sand Shaley	288
30	Shale	318
10	Lime	328
16	Shale	344
9	Shale SANDY	353
16	Lime	369
8	Chalk Lime	377
1	Coal	378
59	Lime	437
8	Shale Limey	445
22	Shale	467
20	Lime	487
7	Shale & Coal Break	495
51	Lime	546
19	Shale	565
2	Coal	567
27	Shale Sandy Gassy	594
28	Shale Sandy	622
6	Lime	628
5	Shale Limey & Sandy	633
11	Lime	644
7	Shale	651
7	Lime	658
1	Coal	659
21	shale Limey	680
9	Shale	689
6	Shale Limey	695
18	Shale Sandy	713
48	Sandy Shale	761
2	Lime	763
1	Coal	764
3	Shale	767
20	lime	787
5	shale	792
3	Lime Shaley	795
18	Shale	803
1	Coal	804
4	Shale	808
17	Sand Shaley	825
19	eime	844
5	Shale	849
8	lime	857
7	Shale	864
4	Sandy Shaley Lime Slight Odor	868
14	Oil Sand Good Show & Odor	882

OLSON #1
Con't.

14-28-16e

SEP

P/

44	Sandy Shale	926
4	Coal	930
11	Shale	941
2	Lime	943
2	Coal	945
15	Sandy Shale	960
45	Shale	1005
4	Sandy Shale	1009
2	Coal	1011
7	Sandy Shale	1018
<u>7</u>	Sand Good Show & Odor	1025
34	Sandy Shale	1059
33	Shale	1092
3	Coal	1095
36	Sandy Shale	1131
<u>22</u>	Oil Sand	1153
57	Sandy Shale	1210
25	Sandy Shale	1235
1	Coal	1236
16	Sandy Shale	1252
30	Lime Miss.	1282

10 Loads of Water @ \$25.00

2 Hrs. Rig Time @ \$125.00 to Clean Hole & Trip Out.

1252' @ \$5.00 Per Foot

Next 30' @ \$10.00 to Drill Miss. Lime.