


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- REX & MORRIS DRILLING CO.
Farm- Mann No. 1

SEC. 6 T. 29 R. 4E
SE SW SE

Total Depth. 3171
Comm. 4-19-53 Comp. 5-9-53
Shot or Treated.
Contractor. Rex & Morris Drilling Co.
Issued. 8-8-53

County Butler
KANSAS



Elevation. 1281 D.F.

Production. 35 bbls.

CASING:

8 5/8" 156' cem. w/120 sx.
5 1/2" 2742' cem. w/125 sx.

Figures indicate Bottom of Formations.

surface hole	350
lime & shale	425
shale & shells	900
shale & lime	1708
sand	1718
shale	1800
lime	1978
shale	2130
lime	2320
lime & shale	2374
sd lime	2412
lime & shale	2547
shale & lime	2582
lime Arbuckle	2585
lime coring	2677
lime	3157
granite wash	3170
granite	3171
Total Depth	

Tops: Scout	
Lansing	1800
Kansas City	2130
Base Kansas City	2320
Arbuckle	2579
Granite wash	3157
Granite	3171

R.U.S.T. All measures from D.F. Ran
Lane Wells Log. Perf. 10 shots 2674-77. Small
amount water. Perf. 13 shots 2660 $\frac{1}{2}$ -64 $\frac{1}{2}$. 450' water
and scum oil 15 hrs. Test 1/3 bailer water
in 30 mins. Perf. 16 shots 2647-52. Test
2/3 bailer water & trace oil 30 mins.
Perf. 16 shots 2640-45, set bridge plug
@ 2655. Test 30 gals. oil & 30 gals.
water in 16 hrs. Acid 1000 gals. swab &
test 110 B.F.P.H. 1600' off bottom.
100 BW & 10 BO. Perf. 10 shots 2580-83,
set bridge plug @ 2600'. Test 33 G.O.
in 30 mins. 900' O.I.H. and 2 gal. water
in 16 hrs. P.C.P.