

24-28-16E


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - AYLWARD AND WILLIS BROS.  
Farm - Sturdevant No. 1

SEC. 24 T. 28 R. 16E  
SE SE SW

Total Depth. 769  
Comm. 12-10-42 Comp. 12-18-42  
Shot or Treated.  
Contractor.  
Issued. 7-16-49

County. Wilson  
KANSAS



Elevation. 900 ft.

Production. 100,000,000 gas

CASING:

6 1/2" 330'  
L 7/8" 635'

Figures Indicate Bottom of Formations.

soil	2
lime	10
shale	30
water sand	90
shale	100
lime	212
shale	217
lime	270
shale blk	278
lime	328
shale	375
lime shells	425
lime hrd	440
shale	445
sand	460
shale	524
lime hrd	560
shale drk	591
lime	612
slate blk	618
lime	625
slate blk, lime	635
shale lgt	643
sand	653
shale wht	720
gas sand	769
Total Depth	

Well test 600,000 C.F.

R. P. 51 lbs.

New 2" tubing used and  
hole mudded to top

100,000 of gas from 590'

to 610' past up in the 20' lime.

Packer set at 735'.

Cage 763' to 765' with pin-hole  
under packer.