


SKELLY OIL CO.
J. Deutsch No. 1.

SEC. 16 T. 16 R. 13 W
NW SE NE
990' FEL 990' FSL E $\frac{1}{2}$ NE & SW $\frac{1}{4}$ NE $\frac{1}{4}$

Total Depth. 3392'
Comm. 12-22-42 Comp. 1-17-43
Shot or Treated.
Contractor. Claude Wentworth Drlg. Co.
Issued. 4-3-43

County. Barton



Rotary @-3392
CASING:
8 5/8" 316' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface soil, shale & shells	0-332
shale	375
shale & red bed	850
anhydrite	895
shale & shells	1120
salt	1155
salt & shale	1348
shale & shells	1475
shale & brkn lime	1615
lime brkn	1700
lime	1750
lime brkn	1775
lime	1800
lime brkn	1820
lime	2168
lime & shale	2610
lime brkn	2680
shale & lime	2748
lime	2805
shale	2838
lime & shale	2871
lime	3088
lime & shale	3135
lime brkn	3247
(gy cryst & oolitic lime, porous, no shows from 3148-3152)	
lime	3280
lime brkn	3368
conglomerate	3384
dolomite gy cryst	3392
Total Depth.	

Tops: Lansing Lime 3134
Arbuckle Lime 3384

3148-52 porous, no shows
3384-92 porous, no sat.