

24-28-16 E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - AYLMARD-WILLIS BROTHERS
Farm - Van Vickie No. 1

SEC. 24 T. 28 R. 16E
CS/2 NW SE

Total Depth. 778
Comm. 12-15-42
Shot or Treated.
Contractor.
Issued. 7-16-49

Comp. 12-25-42

County. Wilson
KANSAS



Elevation. 970 ft.

Production. 500,000,000 gas

CASING:
6 1/4" 340'
4 7/8" 637'

Figures Indicate Bottom of Formations.

soil	2
clay	12
lime	22
shale	27
water, sand	127
shale, blue	137
lime	225
shale, dark	230
lime soft	260
lime	280
shale, black	290
lime	335
shale	385
lime, sholls	430
lime, hard	445
shale	450
sand	462
shale	480
sand	491
shale	532
lime	570
shale	598
lime	617
slate	623
lime	628
slate	633
shale, white	643
oil sand	655
shale	725
sand	730
sand, gas	778
Total Depth	

Packer set at 746'
Cage set at 776' to 779'
Pin Hole at 748'
Tubed with new 2" tubing
All casing pulled and hole mudded to top.
Volume cut to 500,000 c.f. after well
was tubed with 2" pipe. Pressure around
55 lb.