


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- R. M. WILLIS & ETT  
Farm- Huffman No. 2

SEC. 25 T. 28 R. 16E  
NW NW SE

Total Depth.  $682\frac{1}{2}$  = 687 SIM  
Comm. 7-11-52 Comp. 8-2-52  
Shot or Treated.  
Contractor. Sutcliffe Pipe & Supply  
Issued. 1-29-55

County Wilson  
KANSAS



CASING:

$6\frac{1}{4}$  365  
 $4\frac{7}{8}$  555  
2"  $682\frac{1}{2}$  Pulled

Elevation. \_\_\_\_\_

Production. Abd.

Figures indicate Bottom of Formations.

soil clay	11
shale	19
lime	24
shells, $\frac{1}{4}$ BW	85
shale	129
lime	132
shale	139
lime	224
shale	229
lime	248
shale	260
lime	285
shale	293
lime	342
shale	397
shells	426
shale	436
lime	448
shale	456
sand, 20,000 gas	462
shale	490
shale sandy	502
sand	526
shale	545
lime pink	579
shale	615
lime	635
shale	640
lime	650
shale	663
sand	664
oil, sand	668
sand broken	$671\frac{1}{2}$
sand	676
sand broken	$679\frac{1}{2}$
shale sand $682\frac{1}{2}$ =	687 SIM
Total depth	

Water 654  
Congl. oil smell-664  
S.O. 666 ; Good S.O. 668  
Some good sand 669  
Some good sand  $667\frac{1}{2}$   
Good sand 674  
some broken - some good oil 676

Some oil  $679\frac{1}{2}$   
No oil  $682\frac{1}{2}$   
(No good, mostly water- Plugged and  
abandoned 3-10-54  
T. 1st gas 456; gas inc. 462; T. oil  
sand 664; bottom oil sand 679; Shot  
666-82 w/32 qts.,  $1\frac{1}{4}$  bbl. before  
be bbl. after shot.