


EARL F. WAKEFIELD
Susia Miller No. 1.

SEC.17 T.16 R.13W
NEc SE

Total Depth. 3401'
Comm. 12-31-40 Comp. 1-16-41
Shot or Treated.
Contractor, Earl F. Wakefield
Issued. 2-15-41

County. Barton



CASING:
8 5/8" 54'
5 3/16" 3395'

Elevation.

Production. Pot. 2222 B.

Figures Indicate Bottom of Formations.

surface clay	54	lime w/shale strks	3226
shale	160	lime	3236
shale & shells	558	shale sdy	3239
red rock	678	lime	3285
sand	705	shale	3290
shale & shells	760	lime	3351
red bed	824	lime w/shale strks	3364
anhydrite	930	lime	3395
shale	955	lime Arbuckle	3401
red rock	1100	Total Depth.	
shale & shells	1233		
shale & salt	1465		
shale & shells	1590	Hole filled up over	
shale & lime	1685	night with 2700' of	
lime	1715	oil	
shale & lime	1769		
shale & shells	1790		
lime	1846		
shale red	1855		
lime	1935		
lime brkn	2065		
lime	2102		
shale & lime	2189		
lime	2205		
red rock	2222		
lime brkn	2263		
lime	2274		
shale & red rock	2287		
lime	2309		
shale & shells	2335		
lime	2357		
shale & lime	2412		
shale & shells	2515		
shale	2541		
shale & shells	2575		
shale & lime	2625		
lime	2687		
shale	2700		
lime	2713		
shale & shells	2770		
lime	2780		
shale & shells	2811		
lime	2835		
lime sdy	2855		
lime	2985		
shale w/lime strks	2993		
shale & lime	3035		
lime	3080		
shale	3084		
lime	3088		
shale	3096		
lime brkn	3112		
red rock	3120		
shale & shells	3163		
lime	3179		
shale & lime	3199		
shale	3205		
lime	3217		