

State Geological Survey KANSAS DRILLERS LOG BRANCH

API No. 15 — 009 — 20,900
County Number

Operator

Cities Service Oil Company

Address

209 E. William, 700 Sutton Pl. Bldg., Wichita, Kansas 67202

Well No.

11

Lease Name

Stoskopf

Footage Location

1980' FSL

feet from (N) (S) line

330' FWL

feet from (E) (W) line

Principal Contractor

Duke Drilling Company

Geologist

Well Site

G.D. Honas

Spud Date

4/12/75

Total Depth

3388

P.B.T.D.

Date Completed

4/21/75

Oil Purchaser

Cities Service Oil Company


S. 17 T. 16 R. 13 E. W

Loc. 1980' FSL, 330' FWL

County Barton

640 Acres

N



Locate well correctly

Elev.: Gr. 1951

DF 1954 KB 1956

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28	371'	50/50 Pozmix	275	2% Gel 2% CACL2
Production	7-7/8"	5-1/2"	14	3380'	Howco Lite Class "A"	175 100	.75% CFR2 10% Salt
	DV	Tool	@	818'	50/50 Pozmix	225	.75% CFR2 10% Salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
Open	Hole	3380-3388

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8" O.D.	3364	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
May 8, 1975		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	37 bbls.	MCF	106 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
			3380-3388		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Cities Service Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 11	Lease Name Stoskopf	Oil
S <u>17</u> T <u>16</u> R <u>13</u> ^{EX} _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Log Attached				
				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received


 W. J. Devaney
 Signature
 Region Operations Manager
 Title
 5/15/75
 Date