

11-16-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **IMPERIAL OIL**
 Farm- **Bitter**

No. 1

SEC. 11 T. 16 R. 14W
 NW SW NW

Total Depth. 3433'
 Comm. 12-7-63 Comp. 12-17-63
 Shot or Treated.
 Contractor. Imperial Oil
 Issued. 2-29-64

County **Barton**
KANSAS

**CASING:**

8 5/8" 288' cem w/ 200 sx

Elevation. 1922' KB

Production. **DRY**

Figures Indicate Bottom of Formations.

rock & shale	130
shale & sand	288
shale & shells	328
sand & shale	895
anhydrite	926
red bed shale	1250
shale & shells	1660
red bed & shale	1825
shale & lime	3143
lime	3433' RTD
Total Depth	

TOPS: SMP

Anhydrite	895
Topeka	
Heebner	3064
Toronto	3080
Lansing	3134
Base Kansas City	3358
Chickadee	3358
Arbuckle	3413

DST #1 3140-90 (35' & 50' Zones) Op
 30 min. Rec. 5' mud. ISIP 626#, IFP
 0#, FSIP 558# (SIPs 20 min)

DST # 2 3209-26(90' zone) Op 30 min.
 Rec. 15' mud. ISIP 849#, IFP 28#, FFP
 28#, FSIP 771#. (SIPs time 20 min.)

DST # 3 3280-3317 Op 30 min. Rec. 5'
 mud. ISIP 182#, IFP 28#, FFP 182#, FSIP
 38# (SIPs time 20 min.)

DST # 4 3315-60 (180 & 200' zones) Op
 30 min. Rec. 10' mud. ISIP 297#, IFP
 48#, FFP 48#, FSIP 57#, (SIPs time 20
 min.)