

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


Plotted J.S.
11-16-14W

EARL F. WAKEFIELD.
Templing No. 1.

SEC. 11 T. 16 R. 14W.
CE $\frac{1}{2}$ SE SE

Total Depth. 3351
Comm. 9-26-40 Comp. 10-12-40
Shot or Treated.
Contractor, Earl F. Wakefield
Issued, 11-23-40

County Barton.



CASING.

85 $\frac{7}{8}$ " 58'
5 $\frac{1}{2}$ " 3343'

Elevation.

Production. Pot. 2632 B.

Figures Indicate Bottom of Formations.

shale and sholls	580
red rock and iron	615
red rock and shalo	897
anhydrito	922
shale and lime sholls	1285
salt	1300
salt and shalo	1570
lime and shalo	1647
lime	1725
shalo and lime	1800
lime	1835
shalo and sholls	1975
lime cherty	1986
shalo	2043
lime cherty	2052
shalo	2093
lime	2110
shalo	2120
lime	2127
shalo lime sholls	2210
shalo and lime	2319
shalo and sholls	2620
lime	2641
lime broken	2710
shalo and sholls	2754
lime	2798
shalo and sholls	2842
lime	3006
shalo	3021
lime	3033
lime and shalo	3077
lime	3093
shalo and red rock	3099
shale	3122
lime	3133
shalo	3144
lime K.C.	3149
show of oil 3144-49	
shale	3158
lime	3283
show of oil 3159-3168	
show of oil 3321-3325	
lime	3347
lime	3351

Total Depth.