

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS

27580


CASING RECORD

LOCATION

C NE S1/2 SW NE

SEC 23 T 26 R 14 E.

10" 658 FARM Lauber NO. 1 COUNTY Woodson
 20" 8 1-4 940 COMPANY McCollough Oil Co.
 15 1-2 6 5-8 1192 CONTRACTOR Gene Brinegar,
 12 1-2 41 5 3-16 COMMENCED April 23, 1926. COMPLETED
 TOTAL DEPTH 1293' SHOT QUARTS BETWEEN.



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO McCollough Oil Co.,
 Eureka, Kansas. ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS 8-20-27.

INITIAL PRODUCTION Producer

| Formation | Depth | Formation | Depth |
|----------------------|-------|---------------------------|-------|
| soil & sand | 15 | shale | 995 |
| mud blue | 160 | lime | 1001 |
| lime brown | 167 | slate dark Water 2 1/2 B. | 1007 |
| mud grey | 175 | sand dark | 1015 |
| lime hrd | 190 | shale drk | 1065 |
| lime (Water 195') | 210 | shale light | 1077 |
| slate | 215 | lime hrd | 1080 |
| lime | 355 | shale light | 1125 |
| slate (Little water) | 375 | shale drk | 1140 |
| lime | 430 | shale light | 1153 |
| shale blue | 450 | sand drk (Little gas) | 1164 |
| lime broken | 475 | shale drk (Steel line) | 1192 |
| slate grey | 500 | shale grey | 1197 |
| lime HFW | 520 | sand dark (Gas show) | 1202 |
| slate grey | 540 | sand drk | 1208 |
| lime | 575 | sand dark Oil | 1216 |
| slate grey | 612 | sand Oil | 1293 |
| lime | 626 | | |
| shale | 629 | Total Depth | 1293 |
| lime | 658 | | |
| slate grey | 661 | | |
| lime | 671 | | |
| shale | 765 | | |
| lime | 770 | | |
| shale | 776 | | |
| lime | 780 | | |
| shale | 815 | | |
| lime | 825 | | |
| shale | 863 | | |
| sand HFW | 920 | | |
| lime | 945 | | |
| slate | 949 | | |
| lime | 955 | | |
| shale | 970 | | |
| lime Oswego | 990 | | |