

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

36-32-2E

Company ASHLAND OIL & REF. CO. & W. N. BARTLETT
Farm James No. 3

SEC. 36 T. 32 R. 2E
SE NW SE

Total Depth. 3573'

Comm. 7-26-46


Comp. 8-11-46

Shot or Treated.

Contractor. H. H. & B. Drlg. Co., Inc.

Issued. 11-23-46

County. Sumner KANSAS



CASING:

10 3/4" 247.28' Com
5 1/2" 3504' Com

Elevation. 1129' *uh*

Production. Est. 20 BOPD &
5 BWPD

Figures Indicate Bottom of Formations.

cellar	8
sand	30
anhydrite	75
shale & shells	170
sand	190
shale & shells	256
shale & lime shells	435
shale, lime & shells	675
shale & shells	970
shale	1225
shale & shells	1470
shale	1510
lime	1600
lime	1670
lime	1744
shale & lime	1830
shale & lime shells	1945
lime & shale	2085
shale	2210
sand, brkn lime	2309
shale	2375
shale & shells	2495
shale	2605
brkn shale & sand	2674
lime brkn	2711
lime	2835
lime & shale	2930
shale & limo	3160
shale	3220
lime	3458
black shale & lime	3478
shale	3502
lime	3573
Total Depth	<u>1129</u> -2444

Tops:

Stalnaker no show	2225
K.C. Lime	2709-
Miss. show of oil	3212
Simpson	3491-
Arbuckle water	3502

3491
1129

2362

Perforated in Mississippian
3224-60' w/108 shots.