


SHELL PETRO. CORP.
Schneider No. 3-A.

12-16-14W
SEC. 12 T. 16 R. 14W
NEo SE
330'fr NL 330'fr EL SE $\frac{1}{4}$

Total Depth. 3348'
Comm. 8-28-38 Comp. 9-18-38
Shot or Treated.
Contractor. Crow.Drlg.Co.
Issued. 10-15-38

County. Barton



OCT 15 1938

CASING:
10 $\frac{3}{4}$ " 648'
7 " 3334'

Elevation.

Production. Pot. 3017 B.
Figures Indicate Bottom of Formations. No water.

surface clay	25
sand	31
shale	92
shells	138
shale	378
shale, sand & lime	490
shale & shells	580
red bed	650
shale	873
anhydrite	909
shale & shells	1257
shale & salt	1572
brkn lime	1586
shale & lime	1765
shale & lime strks	1934
sdv lime	1950
shale & lime strks	2028
shale & lime	2122
shale & lime strks	2230
shale & lime	2402
shale & shells	2527
shale & lime	2646
shale & lime strks	2741
shale & lime	2806
lime	3070
lime & shale	3106
lime	3179
cherty lime	3192
lime	3334
dolomite	3336
3336 equals 3335 SLCorr.	
dolomite	3348
Total Depth.	

Good porosity 3119-42
Lgt oil stain 3142-61
Oil stain 3191-3213
SLCorr. 3336=3335
Core #1 3338-41
Small amt por., fair oil stain
Oil 2925-3341
Core #2 3344-46
Lgt oil stain
Core #3 3346-48
2950' oil 3348