

State Geological Survey
WICHITA FALLS DRILLERS' WELL LOG

15-009-21155
15-16-14W

DATE COMMENCED: May 5, 1977
DATE COMPLETED: May 13, 1977

Cities Service Oil Company
MILLER Y-2
C W/2 SW
Sec 15-T16-R14W
Barton County, Kansas

ELEVATION: 1936 K.B.

0 - 45'	Surface Soil, Post Rock
45 - 490'	Shale, Sand Streaks
490 - 912'	Red Bed
912 - 943'	Anhydrite
943 - 1585'	Shale
1585 - 2275'	Shale and Lime
2275 - 2861'	Lime and Shale
2861 - 3093'	Lime
3093 - 3096'	Shale
3096 - 3109'	Lime and Shale
3109 - 3126'	Lime
3126 - 3161'	Shale
3161 - 3358'	Lime
3358 - 3378'	Lime and Shale
3378 - 3428'	Lime, Shale, Chert & Sand
3428 - 3460'	Dolomite
3460'	RTD

FORMATION TOPS

Anhydrite	912
Topeka	2861
Heebner	3093
Toronto	3109
Douglas	3126
Lansing K.C.	3161
Base K.C.	3358
Conglomerate	3378
Arbuckle	3428
RTD	3460

SURFACE PIPE:
Set new 8 5/8", 24# pipe
at 280' w/150 sacks 50/50
Pozmix, 2% @c.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 16th day of May, 1977.

Robert M. Hague
Notary Public

Commission Expires: April 11, 1978