

21 - 16 - 14W ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- LEO G. WETHERILL, JR.
 Farm- Haas No. 1

SEC. 21 T. 16 R-14W
 SE SE SE

Total Depth. 3462'
 Comm. 7-30-64 Comp. 8-8-64
 Plot or Treated.
 Contractor. Vaughan Drilg., Inc.
 Issued. 4-17-65

County Barton
 KANSAS



CASING:

8 5/8" 310' w/160 sx cem.

Elevation. 1943' K.B.

Production. DRY

Figures Indicate Bottom of Formations.

surface soil, post rock	40
sandstone, shale	65
shale, clay	265
sandstone	300
shale	356
hard sandstone	360
sandstone	420
hrd sandstone	439
shale, sandstone	500
shale, sand strks	535
red bed	922
Anhydrite	958
shale	1010
shale w/lime strks	1495
limestone, shale	1860
limestone	2120
limestone, shale	2280
shale w/lime strks	2745
limestone, shale	2877
limestone	3099
Heebner, shale	3103
limestone, shale	3169
limestone	3462
Total Depth	

TOPS: SCOUT	S 1
Anhydrite	938
Topeka	2867
Heebner	3100
Toronto	3115
Lansing	3167
Conglomerate	3386
Arbuckle	3430