

24-16-14W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - THE DERBY OIL COMPANY
Farm - Siemsen No. 2

SEC. 24 T. 16 R. 14W
NE SE NE

Total Depth. 3363'
Comm. 8-29-46 Comp. 9-20-46
Shot or Treated.
Contractor. G. W. Peel
Issued. 12-7-46

County. Barton
KANSAS



Elevation. 1918^{rh}

Production. Pot. 660 bbls.

Figures Indicate Bottom of Formations.

CASING:
8-5/8" 620' Cem
5-1/2" 3350' Cem

clay & rock	20
shale & shells	241
shale & sand	400
shale & shells	600
red bed	620
shale & shells	893
anhydrite	923
shale & shells	1320
salt & shale	1495
lime & shale	1540
shale & shells	1595
anhydrite	1718
lime & shale	1918
shale	1926
lime with cherty strks	1956
lime	1967
lime & shale	2349
shale & shells	2427
lime & shale	2770
shale	2824
lime	2855
cherty lime	2865
lime	3074
lime & shale	3134
lime	3363.
Total Depth	

deeper to 3362 $\frac{1}{2}$. Swabbed 33
BOPH for 3 hrs. 300' off
bottom. ~~No water~~.
1000A by Chemical Process Co.,
Swabbed 32 BOPH for 3 hrs. off
bottom. No water. Drilled
deeper to 3363 $\frac{1}{2}$ (-1445 $\frac{1}{2}$) TD.
1500 gal. Dowell XX acid with
Pilot. Swabbed 36 BOPH for 3
hrs. 700' off bottom. No water.

Tops:
Lansing 3134
Arbuckle 3349
Rot. Total Depth 3352

Cable Tool Work:
Drilled plug and drilled
deeper to 3354'. Swabbed
15 BOPH for 3 hrs., off
bottom. No water. 500A by
Chemical Process Co.
Swabbed 16 BOPH Drilled