

23-16-14-10


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- REX & MORRIS & C. R. A.
Farm- Templing No. 1

SEC. 23 T. 16 R. 14W
SE NE NW

Total Depth. 3426 D.F.
Comm. 8-10-55 Comp. 9-1-55
Shot or Treated.
Contractor. Rex & Morris Drilling Co.
Issued. 11-5-55

County Barton
KANSAS



8 5/8 @ CASING: 223' w/ 150 sx cmt.
5 1/2 @ 3413' w/ 125 sx cmt.

Elevation. 1960 DF
Production. 4 BOPH

Figures Indicate Bottom of Formations.

surface hole	228
shale & shells	900
lime & shale	955
broken lime	1085
shale & shells	1275
shale & lime	2868
lime	3026
shale & lime	3164
lime	3388
conglomerate	3411
lime	3413
Rust, DP & Co. no shows	
RTD (RB)	3410
RTD (DF)	3412
white lime, no shows	3415
lime & dolomite	3420
brown lime	3424
light lime	3426
brown lime w/ staining	
Total Depth (DF)	
SCOUT TOPS:	
Topeka	2866
Heebner	3097
Lansing	3164
Arbuckle	3411

small amount oil stain @ 3413
no shows @ 3415
odor oil @ 3417
washed free oil @ 3419
test 1/2 gal oil/30 min. @ 3420
no inc. @ 3424

Test 16 hrs. 44.5 GO, 10.2 GW
test 3 hrs. 6 GO w/ tr. wtr.
acid 500 gal. swb down test 5 1/2 BW &
tr. oil/30 min.
test 7 1/2 BW & tr. oil/30 min.
test 2150' wtr. & 50' oil/13 hrs.
PB 3370, perf/ 32/3352-60, no fluid.
test 16 hrs. no fluid, acid 1000 gal.

swb. down.
test 4 1/2 BO/30 min. Decr. /3 hrs to 4 BOPH
FU 2135' oil/14 hrs. Final test 4 1/2 BOPH
PB 3345' perf/ 32/3332-40 test 4 1/2 BOPH
test 10 1/2 BO/14 hrs. acid 1000 gal
swab down. test 4 BOPH/7 hrs.
DP to 3370' test 4 BOPH/6 hrs. test 1750' oil/14 hrs.
test 8 BOPH/6 hrs. test 4 BOPH/7 hrs.