

23-16-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- REX & MORRIS & C. R. A.
Farm- Templing No. 2

SEC. 23 T. 16 R. 14W
NW NE NW

Total Depth. 3409
Comm. 10-7-55 Comp. 10-27-55
Shot or Treated.
Contractor. Rex & Morris Drilling Co.
Issued. 12-24-55

County Barton
KANSAS



CASING:
8 5/8 @ 918' w/ 500 sx cmt.
5 1/2 @ 3402' w/ 125 sx cmt.

Elevation. 1951 DF

Production. 50 BOPD

Figures indicate Bottom of Formations.

shale, sand & lime	685
shale & shells	912
anhydrite	922
red bed	1050
shale & shells	1600
lime & shale	2105
lime	2180
lime & shale	2860
lime	3050
lime & shale	3159
Lansing lime	3367
shale & pyrite	3376
lime	3381
conglomerate	3400
Arbuckle lime RTD(RB)	3402
D.U.S.T.D.P. & CO. RTD (DF)	3399
cherty lime, oil stains	3402.5
cherty dolomite	3405
brown dolomite, odor	3407
brown dolomite, small scum oil	3408
brown dolomite, small amount	3409
free oil	
Total Depth	

SCOUT TOPS:

Anhydrite	912
Topeka	2860
Heebner	3092
Toronto	3107
Lansing	3159
Conglomerate	3181
Arbuckle	3400

Test 35 GO, 1 GW/14 hrs.
Acid 500 gals. chase w/ 83 BO,
Swab down 79 BO, test 2 1/2 BOPH/4 hrs.
Test 750' oil & 100 gal acid wtr/13
hrs.
Test 24 hrs. . Final test 2.03 BO, NW