

25-16-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO., INC.
Farm- Chaloupka No. 1

SEC. 25 T. 16 R. 14W
SW SW NE

Total Depth. 3468
Comm. 11-9-51 Comp. 11-19-51
Shot or Treated.
Contractor. Peel Bros. Inc.
Issued. 3-1-52

County Barton
KANSAS



CASING:
8 5/8" 560' cem.
5 1/2" 3426' cem.

Elevation. 1968 R.B.
1966 (m)

Production. 10 BOPD NW

Figures indicate Bottom of Formations.

surface clay	80
sand & shale	145
shale & shells	250
sandy shale	325
shale, shells & sand	560
shale & red bed	945
anhydrite	970
shale & shells	1220
salt & shale	1330
shale	1640
shale, lime & shells	1735
lime & shale	2635
shale, lime & shells	2815
lime & shale	3175
lime	3401
congl.	3420
arbuttle	3432
lime	3468
Total Depth	

Swb. 1 BOPH 24 hrs. 500 Channel A.
3000 A. Hydrafrac. Swb. approx.
1 BOPH

Tops:
Heebner 3118
Lansing 3192
Congl. 3417
Arbuttle 3420

DST: 3204-40 open 1 1/2 hrs.
rec. 780' salt wtr. BHP 450#.
DST: 3371-3401 open 1 1/2 hrs.
rec. 60' OCM w/little free
oil BHP 760#.
RTD 3432'
DD 3439 500 A.
DD 3453 1/2 1000 A.
DD 3468
Plug 3385 36/3373 1/2-79 1/2 N.S.
500A.
Swb. 75 BOPH, NW 2000 A.