

15- 009 - 21839
24-16-15W

State Geological Survey
WICHITA, BRANCH

DRILLER'S WELL LOG

DATE COMMENCED: 3-4-80
DATE COMPLETED: 3-14-80

Bankoff Oil Company
Ochs #1
NW SW NE, Sec. 24-16-15
Barton County, Kansas

ELEVATION: 1971' K.B. 1967' D.F.

FORMATION DATA

84-1010' Anhydrite
3139-3144' Shale
3144-3158' Lime
3158-3207' Lime
3207-3424' Lime
3424-3462' Lime and Shale
3462-3481' Dolomite
3481' RTD

Anhydrite 984'
Heebner 3139'
Toronto 3158'
Kansas City 3207'
Base Kansas City 3424'
Arbuckle 3462'
RTD 3481'

SURFACE PIPE:
Set 259' used 8 5/8" casing
28# w/160 Sacks Common
60/40 Pozmix, 2% gel, 3% cc

PRODUCTION PIPE:
Ran 83 jts, 5 1/2", 14# casing
Set @ 3480' w/ 125 sacks
60/40 Pozmix salt saturated
10 bbls. salt flush ahead
Job completed @ 7:30 a.m.
3-14-80 by Sun Cement

MAR 24 1980

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.