

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


22-16-14W

Company- IMPERIAL OIL
 Farm- Miller "B" No. 1

SEC. 22 T. 16 R. 14W
 NE NW NW

Total Depth. 3476'
 Comm. 8-6-63 Comp. 8-15-63
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 11-30-63

County Barton
 KANSAS



CASING:

Elevation. 1951' KB

8 5/8" 278' cem w/ 225 sx

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	935
anhydrite	965
shale & red bed	1460
shale & shells	1750
lime & shale	2925
lime	3430
lime & chert	3476
Total Depth	

TOPS: SMP

Top Anhydrite	.935
Base Anhydrite	965
Heebner	3111
Toronto	3127
Lansing	3179
Base Kansas City	3393
Arbuckle	3470

DST #1 3181-3201' Op 30 min. Rec. 10' mud
 with a trace of oil. All pressures zero

DST # 2 3316-94' Op 30 min. Rec. 20' mud. ICIP
 567# 20 min, IF 28#, FF 28#, FBHP 192 #
 20 min.