

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

Company DERBY OIL CO. & GLENN W. PEEL
Farm Siemsen No. 1

SEC. 24 T. 16 R. 14 W
NEc NE

Total Depth. 3352'

Comm. 2-20-46

Comp. 3-13-46


Shot or Treated.

Contractor. Glenn W. Peel

Issued. 5-25-46

County. Barton

KANSAS



Rotary 3349'
Cable 3349-52'

CASING:

8 5/8" 623' Cem.
5 1/2" 3347' Cem.

Elevation. 1919 ft

Production. Deptho. Pot. 618

Figures Indicate Bottom of Formations.

clay	0-50
sand	70
shale	110
shale & shells	615
shale red	632
shale & shells	890
anhydrite	925
shale & shells	1265
shale salts	1563
shale	1595
lime	1763
shale & shells	1950
lime	1980
lime & shale	2030
shale	2225
shale & shells	2410
lime & shale	2590
lime	2695
lime & shale	2825
lime & cherty	
strks	2887
lime	2989
cherty lime	3004
shale & lime	3057
lime	3352
Total Depth.	

9 BOPH for 5 hrs. - no wtr.

All Measurements are from DF
which was 7.70 to Bradenhead.

Tops:

Lansing 3127
Arbuckle 3344

T.D. w/rotary 3349'

CABLE TOOL WORK

Drilled plug & cleaned out to
3349' - 800' oil 3 hrs. Drilled
deeper to 3352' TD. - 1600' oil
8 hrs. Swab test off btm. -
11 BOPH for 3 hrs. - no wtr.
acidized w/500 gals. Swab
test off btm after acid. -