


25-16-14W

Company - PHILLIPS PETRO.CO.
 Farm - Putnam No. 1.

SEC. 25 T. 16 R. 14 W
 SE NE SW

Total Depth. 3483'
 Comm. 8-30-44 Comp. 9-27-44
 Shot or Treated.
 Contractor.
 Issued. 11-11-44

County. Barton
 KANSAS



CASING:
 8" 634'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	35- 540
sand	562
lime & shale	640 ¹ / ₂
red bed, shale & shell	934
anhydrite	959
shale & shells	1415
salt, shale & shells	1635
lime	1845
shale & shells	1935
lime	2000
chert	2015
lime	2084
shale & shells & lime	2115
lime & shale	2265
lime	2306
shale	2560
shale & shells	2670
lime & shale	2745
shale	2830
lime & shale	2975
lime	3000
lime & shale	3267
lime	3415
lime & shale	3419
chert & lime	3437
congl	3452
chert	3459
Arbuckle lime	3483
Total Depth	

Tops:

Lansing KC	3191
Congl	3412 w/no shows
Arbuckle	3451 w/no shows
Had Porosity but no sat.	
3469-3475. Dry & Abd.	