

26-16-1-43


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- A. Scott Ritchie
Farm- Batt "B" No. 2

SEC. 26 T. 16 R. 14W
SW NW SE

Total Depth. 3460'
Comm. 4-6-65 Comp. 4-14-65
Shot or Treated.
Contractor. Hellar Drilling Company, Inc.
Issued. 7-24-65

County Barton
KANSAS



Elevation. 1951' KB

Production. 32 BOPD Plus 72% Water

CASING:

8 5/8" 346' cem w/210 sx.
4 1/2" 3447'

Figures Indicate Bottom of Formations.

post rock-shale and sand	346
shale	373
shale and shells	912
anhydrite	937
shaled red beds	970
red beds and shale	1346
shale	1656
lime and shale	1765
lime	1935
Ft. Riley	2100
lime and shale	2960
lime and shale stks.	3052
lime and shale	3125
Douglas	3160
Lansing-Kansas City	3176
Kansas City	3178
lime	3375
shale and lime	3418
shale and lime & lot of chirt	3455 ETD
Total Depth	

Tops: LOG	
Amydrite	912
Topeka	2866
Heebner	3096
Toronto	3111
Lansing	3165
Base Kansas City	3374
Conglomerate	3389
Arbuckle	3449