

29-16-14W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East ^Wurdock, Wichita, Kansas

Company - MUSGROVE PETROLEUM CORP., INC.
Farm - J. Popp, Jr. No. 1

SEC. 29 T. 16 R. 14W
SE SE SW

Total Depth. 3490
Comm. 7-26-50 Comp. 8-8-50 ✓
Shot or Treated.
Contractor. Jackson Drilling Corp.
Issued. 10-7-50

County. BARTON
KANSAS



CASING:
8 5/8" 657' cem w/350 sx.

Elevation. 1996 DF
1998 *2nd*
Production. dry

Figures Indicate Bottom of Formations.

All measurements from top of derrick floor.

clay	90
sand	100
shale	360
shale, lime shells	470
sand, shale, pyrite	535
sand	620
lime, sand, shale	658
red bed	984
anhydrite	1010
red bed, shale, shells	1390
red bed, salt, shells	1670
shale, lime	1710
lime	1855
shale, lime	1960
lime	2150
lime, shale	2460
shale	2500
shale, shells	2627
shale	2680
lime, shale	2878
lime	2896
shale	2920
lime	3448
lime, shale	3462
conglomerate	3474
sandy lime, cherty	3480
arbuckle lime	3490
Total Depth	

Tops:

Heebner	3153
Toronto	3168
Lansing-K.C.	3216
Simpson Shale (?)	3443
Arbuckle	3482

DST: 3222-3252