

**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**

508 East Murdock,


Wichita, Kansas

Company. **IMPERIAL OIL COMPANY**  
 Farm. Robison No. 1

SEC. 34 T. 16 R. 14W  
 150' N/ C NE NE

Total Depth. 3458'  
 Comm. 3-26-64 Comp. 4-9-64  
 Shot or Treated.  
 Contractor. Company Tools  
 Issued. 6-13-64

County Barton  
 KANSAS



Elevation. 1947' KB

Production. Dry

**CASING:**

8 5/8" 309' cem w/200 sx.

Figures Indicate Bottom of Formations.

post rock & shale	309
shale-sand-redbed	917
Anhydrite	944
shale-shells	1615
shale-lime	2800
lime	3458 RTD
Total Depth	

**TOPS: SAMPLE**

Anhydrite	917
Topeka	2867
Heebner	3102
Toronto	3116
Lansing	3168
Base Kansas City	3390
Conglomerate	3414

DST #1 3174-90' Op. 1½ hrs. Rec. 140'  
 muddy wtr.. ICIP 976#/20", IFI 19#, FF  
 86#, FBHP 888#/20".

DST #2 Op 2 hrs. Rec. 180' gas in pipe  
 30' slightly oil cut mud. ICIP 96#/20".  
 IF 19#, FF 19#, FBHP 19#/20".

DST #3 3312-90' Op. 1½ hrs. Rec. 180'  
 gas in pipe, 30' mud. ICIP 67#/20", IF  
 19#, FF 19#, FBHP 38#/20".

No Electric Log was run.