


35-16-14W

Company - MAGUIRE INDUSTRIES, INC.
 Farm - Logan No. 1.

SEC. 35 T. 16 R. 14 W
 S E NW NW

Total Depth. 3474'
 Comm. 10-23-44 Comp. 11-15-44
 Shot or Treated.
 Contractor. Donald T. Ingling
 Issued. 12-23-44

County. Barton
 KANSAS



CASING:
 8 5/8" 310'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sur. clay rock	
& sdy shale	75
sdv shale & shells -	
red rock	257
sand	275
shale, shells & iron	305
red rock	330
sand & shale	400
sand sharp hrd	460
soap-stone, gyp &	
shale	543
shale sdy & shells	615
red bed & shale	905
anhydrite	955
shale sdy & red rock	1200
shale & shells	1320
shale & salt	1520
shale & shells	1540
lime sdy & shale	1690
shale & shells	1760
lime sdy & shale	2020
lime sdy	2178
lime sdy & shale	2350
lime & shale	2540
shale & shells	2650
lime & shale	2822
lime	3000
lime hrd	3030
lime	3200
lime hrd	3209
lime sft	3219
lime hrd	3350
lime hrd sdy	3397
lime	3415
cherty conglomerate	3474
Total Depth	

Tops:

Lansing 3185
 Cherty Cong. 3409-74

T.D. in congl. 3474