

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NE cor SW/4

Sec. 9 T. 25 R. 13E.

Casing Record

County- Greenwood.

20" 10" 474
 15 1/2" 8 1/4" 1108'
 12 1/2" 21 65/8" 1510
 53/16"

Farm- Tatman
 Company- Mendenhall & Son.
 Contr.-
 Comm.- 5/8/29.

No. 1


Comp.- 6/26/29.

Total Depth 1535'.

Shot

Quarts Between

Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production 30 bbls.

Date Issued. 7/20/1929.

Formation	Depth
soil	21
lime	25
light shale	70
lime	75
drk shale	85
light shale	100
lime	120
light shale	160
lime	165
sand	190
light shale	200
sand	210
light shale	260
lime	265
light shale	275
lime	285
sandy shale	300
shale muddy	425
lime	430
blue sand	455
lime	570
light shale	726
lime	740
light shale	745
lime	749
light shale	754
red rock	764
light shale	779
lime	784
shale	792
lime 2 BW 840 in lime	862
drk shale	875
lime	893
drk shale	897
lime	931
sandy lime	960
drk shale	1073
lime	1078
light shale	1108
lime	1125
shale	1155
lime	1160
light shale	1180
lime	1185
light shale	1190
lime	1200
blue shale	1208
lime	1212
drk shale	1230
lime	1252
drk shale	1257
lime	1264
light shale	1274
lime	1277
light shale	1440
sand	1455
drk shale	1512
Top of oil sand	
oil sand	1525
sand	1532
shale	1535
TD	1535'

Water.

HFW