

36-16-14W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

PHILLIPS PETRO. CO.
Addie No. 1.

SEC. 36
SEc NE


T. 16

R. 14 W

Total Depth. 3459'
Comm. 5-25-43 Comp. 6-24-43
Shot or Treated.
Contractor.
Issued. 10-16-43

County.

Barton



CASING:
8 5/8" 615' Cem.
5 1/2" 3436' Cem.

Elevation.

Production. Salt Wtr Disp.

Figures Indicate Bottom of Formations.

shells & sdy clay	166
red rock & shale	506
red rock	540
sand	555
gyp & sand	600
red rock	940
anhydrite	981
shale & red rock	1712
sdv lime & shale	1936
shale & lime	2291
shale & lime shells	2491
shale	2691
shale & lime	3048
lime	3107
shale & lime	3226
lime	3357
shale & lime	3412
lime	3438
lime, coring	3441
very sm sh oil after setting 8 hrs	
lime	3459
Total Depth.	

Tops:

Lime 3227
Arbuckle 3429

sm sh oil after setting 4 hrs
1st test 63 gals. oil, no wtr
3rd test 180' oil, no wtr
5th test 300' oil, no wtr
6-21-43 no oil or wtr 3441-44
no oil or wtr 3444-46
poor rec. 3446-49
6-22-43 445' oil in hole at
8 A.M., no wtr
525' oil in hole at
2:45 P.M., no wtr
Water increased to HFW