

36-16-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO., INC.
Farm- Fleming No. 1

SEC. 36 T. 16 R. 14W
SW SW NE

Total Depth. 3461
Comm. 8-19-51 Comp. 8-31-51
Shot or Treated.
Contractor. Anschutz Drlg. Co., Inc.
Issued. 11-3-51

County Barton
KANSAS



CASING:

8 5/8" 568' cem w/250 sxs.
5 1/2" 3458' cem w/150 sxs.

Elevation. 1983 DE

Production. 203 bbls & 7% wtr.

Figures Indicate Bottom of Formations.

lime	100
sand	115
shale, shells	340
sand	370
shale, shells	584
red bed	953
anhydrite	985
red rock, shale, salt	1305
shale, shells	1640
shale	1675
lime	1790
lime, shale	1920
sandy lime, shale	2050
broken lime	2240
lime, shale	2570
shale, shells	2705
shale, lime	2900
lime	3438
conglomerate, lime	
arbuckle	3461
Total depth	

Tops:
Heebner 3141
Lansing 3215
Conglomerate 3434
Arbuckle 3456