


SEC 9 TWP. 29S. RG. 4 E
 #2 Minor FARM
 Butler, Coutny, Kansas.



COMPANY: OHIO OIL

CONTRACTOR:

DRILLING COM:

DRILLING COMP:

CASING RECORD: 15½	70#	20'
12½	50	482
10	35	297
10	32	895
8¼	28	225
8¼	24	1390
6¼	24	1785

STRATA	THICKNESS	TOTAL DEPTH	STRATA	THICK	DEPTH
Soft black Shale	10	15.	White Lime (2 Blrs. W)	50	1510
Hard white Gravel	10	25	Dark Shale (Cave)	30	1540
Hard white Lime	45	70	White Lime	35	1575
Soft blue Shale	3	73	Dark Shale (Cave)	39	1614
Hard blue Lime (1 Blr)	31	104	(18 blrs. water at 1552')		
Yellow clay	9	113	Dark Lime (8¼ csg.)	8	1622
Blue Lime	27	140	White Slate	151	1773
Black Slate	32	172	Hard Gas Sand	3	1776
Soft Black Lime	31	203	Hard White Shell	7	1783
White Slate	17	220	Hard Oil Sand	5½	1788½
Hard white Lime	15	235	Hard White Lime	8½	1797
Soft black Shale	30	265	Soft white Lime	1	1798
Soft red Shale	10	275			
White lime	40	315			
White Slate	10	325			
White Lime	10	335			
Soft white Slate	20	355			
Soft white Lime	93	448			
(1 bailer water)					
Soft Black Slate	22	470			
Hard Black Lime	25	495			
Soft white Shale	305	800			
Hard white Lime	25	825			
Soft dark Shale	20	845			
Hard white Lime	25	870			
Soft white Shale	70	940			
Hard white Lime	210	1150			
Soft white Shale	15	1165			
Hard white Lime (Csg. 1192)	53	1218			
Blue Shale	10	1228			
Soft blue Lime	16	1244			
Soft Dark Shale	21	1265			
Hard white Lime	15	1280			
Soft white Shale	28	1308			
Hard dark Lime	26	1334			
Dark Shale (Cave)	11	1345			
Black Lime (Cave)	37	1382			
Light Shale Light	36	1418			
White Lime	17	1435			
Light Shale	25	1460			

Log.

MIXOR NO. 2.

Ohio Oil Co

9-29 south-4 east.
Butler County, Kansas.

24102

Shale	black	soft	10	15	
Gravel	white	hard	10	25	
Lime	white	hard	45	70	
Shale	blue	soft	3	73	
Lime	blue	hard	31	104	1 bailer
Clay	yellow		9	113	water.
Lime	blue		27	140	
Slate	black		32	172	
Lime	black	soft	31	203	
Slate	white		17	220	
Lime	white	hard	15	235	
Shale	black	soft	30	265	
Shale	red	soft	10	275	
Lime	white		40	315	
Slate	white		10	325	
Lime	white		10	335	
Slate	white	soft	20	355	
Lime	white	soft	93	448	1 bailer
Slate	black	soft	22	470	water.
Lime	black	hard	25	495	
Shale	white	soft	305	800	
Lime	white	hard	25	825	
Shale	dark	soft	20	845	
Lime	white	hard	25	870	
Shale	white	soft	70	940	
Lime	white	hard	210	1150	
Shale	white	soft	15	1165	
Lime	white	hard	53	1218	Csg. 1192
Shale	blue		10	1228	
Lime	blue	soft	16	1244	
Shale	dark	soft	21	1265	
Lime	white	hard	15	1280	
Shale	white	soft	28	1308	
Lime	dark	hard	26	1334	
Shale	dark		11	1345	Cave.
Lime	black		37	1382	Cave.
Shale	light		36	1418	
Lime	white		17	1435	
Shale	light		25	1460	Cave.
Lime	white		50	1510	2 bailers
Shale	dark		30	1540	water at
Lime	white		35	1575	1500 feet.
Shale	dark		39	1614	18 bailers
Lime	dark	8 1/2" Csg.	8	1622	water at
Slate	white		151	1773	1552 feet.
Sand Gas		hard	3	1776	
Shell	white	hard	7	1783	
Sand Oil		hard	2 1/2	1788 1/2	
Lime	white	hard	8 1/2	1797	
Lime	white	soft	1	1798	1 bailer

Total Depth