


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- L. C. McLAUGHLIN
Farm- Davidson No. 6

SEC. 33 T. 28 R. 16E
SE N/2 NW

Total Depth. 998
Comm. 8-10-55 Comp. 8-25-55
Shot or Treated.
Contractor. McLaughlin Drlg Co.
Issued. 7-7-56

County Wilson
KANSAS



CASING:
10" 8' 4" 988'
8 1/2" 420' 2" 997'
7" 731'

Elevation. _____

Production. 25 bbls

Figures indicate Bottom of Formations.

soil	4
clay	15
shale	20
shells	66
lime	86
shale sdy	93
shale	100
lime sdy	145
4 BWH @ 140	
10 to 12 BWH @ 185	
shale	185
lime	288
shale	323
lime	336
shale	341
lime	345
shale	348
lime	405
shale	448
lime	451
shale	470
shells	485
lime	495
shells	505
lime RRS	524
shale, shells	565
shells	600
shale	612
lime	648
shale blue	660
shale lgt	676
shale RSL	685
lime	705
shale, slate	709
lime	729
shale lgt	731
shale	733
lime sdy	751
shale, shells- Bailed	
hole	775
shells	785
shale	800
lime	803
shale	820
shale sdy	850
shale	864
shale sdy	885
sand Free oil on	
30 test. RSL	891
Cored from 981-	902.4
Plugged back to	998
Total Depth	
Lead Wool back to	988
Top of oil snad	988

25 sxx cem.
1-10-56 Frac'd by Halliburton
Oil shows: 12 BO before shot
25 BO after shot.