


19-32-3E



10" FARM Carson
50" 36 8 1-4 COMPANY T. B. Slick
15 1-2 6 5-8 CONTRACTOR
42 1-2 1338 5 3-16 COMMENCED Aug 6, 1925
TOTAL DEPTH 2615

NO. 5B COUNTY Cowley

COMPLETED Sept 9, 1925

SHOT QUARTZ BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO. T. B. Slick.
Oklahoma City, Okla.

ELEVATION.

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 262½ bbls
in 18 hr.

REMARKS

Formation Depth

sand 26
blue shale (set 36" 20' 135)
light lime 140
blue shale 155
lime shells 165
blue shale 175
lime 177
red bed 183
lime white 190
grey lime 270
lime 275
blue shale 340
light lime 360
blueshale 365
lime 375
white lime 400
blue shale 405
red rock 415
lime shells 430
grey lime 480
light lime 500
broken lime shells 530
lime 555
red rock 575
blue shale 585
grey lime 588
white lime 615
blue shale 622
white lime 640
blue shale 645
dark lime 715
shale 720
lime blue very hard 775
lime shells 785
blue shale 860
lime 865
shale 910
dark lime 920
shale dark 935
lime shells 945
blue shale 995
lime shells 1000
blue shale 1038
lime 1040
blue shale 1075
dark lime 1120
slate 1130
dark lime 1160
slate dark 1170
grey lime 1200

Formation Depth.

grey lime 1235
dark shale 1275
blue slate 1310
lime 1315
sand 1325
lime 1330
shale (set 12½@1338) 1338
dark slate 1348
light lime 1358
dark shale 1370
light lime 1374
dark shale 1430
hard lime 1435
blue shale 1450
dark lime 1450
dark shale 1515
dark lime 1555
black shale 1560
lime 1565
grey shale 1590
lime 1615
shale 1618
lime 1628
shale 1631
lime 1660
dark slate 1710
lime shells 1730
dark shale 1810
lime 1820
slate 1835
lime 1845
dark shale 1885
Lime HFV 1890 1905
slate blue 1980
black slate 2165
sandy lime 2185
dark slate 2190
water sand broken Lime 2258
black slate 2360
broken lime 2575
slate 2595
oil sand 2621
fir showing oil 2595
good flow og gas and more oil 2610
pay sand 2615