

32-16-16W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRONTIER OIL CO.
Farm- Allen No. 1

SEC. 32 T. 16 R. 16W
NE NE SE

Total Depth. 3585'
Comm. 6-13-64 Comp. 6-22-64
Shot or Treated.
Contractor. Red Tiger Drlg. Co.
Issued. 12-12-64

County Rush
KANSAS



Elevation. 1989' D.F.

Production. GA 470 MCFGPD-SIGW

CASING:

8 5/8" 211.53' w/135 sx cem.
4 1/2" 3111' w/150 sx cem.

Figures Indicate Bottom of Formations.

sod, clay	50
Post Rock, clay	100
shale, sand	130
shale	215
shale, shells, red bed	354
sand, shale	365
shale, shells	405
sand strks, shale	555
sand	715
red bed, shale	1087
Anhydrite	1125
red bed, shale	1390
shale, shells, red bed	1472
shale, salt	1585
shale, shells	1803
shale, lime	2310
shale	2495
shale, lime	3073
lime	3520
lime, chert	3578
lime	3585
Total Depth	

TOPS: SCOUT	SAMPLE
Anhydrite	1087
Topeka	2993
Heebner	3225
Lansing K.C.	3280
B/Kansas City	3508
Conglomerate	3520
Arbuckle	3557