

31-16-16W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRONTIER OIL COMPANY
Farm- Honderick "A" No. 1

SEC. 31 T. 16 R. 16W
C NW

Total Depth. 3617'
Comm. 2-14-63 Comp. 2-24-63
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 6-1-63

County Rush KANSAS



Elevation. 2007' DF

Production. Dry

CASING:

8 5/8" 209' cem w/135 sx.
4 1/2" 3180.08' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface	70
shale	80
shale w/rock stringers	209
shale clay & sand strks.	543
Dakota Sand	764
red bed shale	1121
Anhydrite	1158
shale & shells	1585
salt	1630
shale & shells	1780
shale & lime	3270
lime	3591
Arbuckle	3617 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1121
Topeka	3029
Heebner	3260
Lansing-Kansas City	3315
Base Kansas City	3543
Cherty Conglomerate	3566
Reworked Arbuckle	3590
Arbuckle	3608