

COPY

24132

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY


719-720 Union National Bank Bldg., Wichita, Kansas

CASING RECORD

LOCATION SW c SE/4 NE/4

SEC 9 T 29 R 4 E.

10" FARM R. B. Patterson NO. 6 COUNTY Butler
 20" 8 1-4 COMPANY Mid-Kansas Oil & Gas Co.
 15 1-2 6 5-8 CONTRACTOR
 12 1-2 5 3-16 COMMENCED COMPLETED



TOTAL DEPTH 1808'.

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO
 Co., El Dorado, Kansas.

Mid-Kansas Oil & Gas

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS

INITIAL PRODUCTION

REMARKS

Formation	Depth	Formation	Depth
soil	10	lime white	1070
slate white 24' of 15 $\frac{1}{2}$ "	25	slate white	1125
lime white	50	slate blk	1140
rock red	55	lime white	1160
slate blk	80	lime white	1175
lime white	110	1172--10" csg.	
slate white	120	slate blk	1190
lime white	150	lime white	1200
slate blk	160	slate blk	1255
rock red	170	slate white	1286
lime white	210	lime white	1315
slate blk	270	slate blk	1335
lime white	280	lime white	1365
slate blk	300	slate & lime	1405
lime & slate blk	375	slate blk	1460
slate blk	425	lime white	1500
lime white	440	slate white	1530
sand white	450	lime white	1545
lime white	475	slate blk HFW	1565
slate & lime white	600	water sand white	1580
490 of 12 $\frac{1}{2}$ " csg.		lime white	1595
slate blk	700	1590' of 8 $\frac{1}{4}$ " csg.	
sand white	715	slate blk	1610
sand white	750	shale	1710
slate blk	770	slate white	1760
slate white	790	shale	1773
lime white	800	lime	1797
lime	835	211 of 6 5/8" liner	
slate blk	860	sand	1808
lime white	870		
slate white	885	Total Depth	1808'.
lime white	890		
slate white	950		
lime white	960		
slate blk	990		
lime white	1020		
slate blk	1050		