

19-16-17W

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **FRONTIER OIL**

SEC. 19 T. 16 R. 17W
 LOC. SE NE NW

FARM **Hooper**

NO. **1**

TOTAL DEPTH **3527**

COMM. **8-21-66**

COMP. **9-1-66**


SHOT OR TREATED

CONTRACTOR **Red T/ger Drlg.**

ISSUED **12-31-66**

COUNTY **Rush**

KANSAS



CASING

20	10		
15	8 5/8"	@ 220'	w/135 SX
12	6		
13	4 1/2"	@ 3525'	w/275 SX

ELEVATION **1995' RB**

PRODUCTION **SIGW/Lans**
3249-3344

FIGURES INDICATE BOTTOM OF FORMATIONS

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Cellar - Postrock	0	115	
Shale	115	518	
Sand	518	720	
Red Bed & Shale	720	1098	
Anhydrite	1098	1139	
Shale & Shells	1139	1815	
Shale & Lime	1815	2360	
Shale & Shells	2360	2875	
Lime & Shale	2875	3180	
Lime	3180	3220	
Lime & Shale	3220	3266	
Lime	3266	3500	
Quartzite	3500	3527	

	1992 DF	--	1995 RB
Elevation			
Anhydrite	1098		(+897)
Topeka	2970		(-975)
Heebner	3201		(-1206)
Lansing-Kansas City	3251		(-1256)
Quartz	3493		(-1498)
Rotary Total Depth	3527		(-1532)
4 1/2" Pipe At	3525		(-1530)

Maxine V. Starr

Subscribed and sworn to before me this 13th day of September, 1966.

Jean Stollar
 Notary Public

My Commission Expires:

5-22-70