

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

21-16-17W

COMPANY FRONTIER OIL

SEC. 21 T. 16 N. 17W  
 LOC. C NW SW

FARM Urban "G"

NO. 2

TOTAL DEPTH 3550

COUNTY Rush


COMM. 3-4-68

COMP. 3-15-68

SHOT OR TREATED

CONTRACTOR Red Tiger Drlg.

ISSUED 5-18-68



CASING

20	10	
15	5/8"	@ 1106' w/250 SX
12	6	
13	5x 4 1/2"	@ 3549' w/50 SX

ELEVATION 1982' KB

PRODUCTION 96 BOPD, NW  
 LANS 3266-74

FIGURES INDICATE BOTTOM OF FORMATIONS

FORMATION	FROM	TO	REMARKS
Post Rock	0	40	
Shale & Shells	40	55	TOPS: SAMPLE
Shale	55	469	
Sand	469	720	Topeka 2982
Red Bed & Shale	720	1096	Heebner 3212
Anhydrite	1096	1135	Lansing 3263
Shale & Shells	1135	1815	Ct Conglomerate 3514
Shale & Lime	1815	2998	Arbuckle 3549
Lime	2998	3045	
Lime & Shale	3045	3125	
Lime	3125	3505	
Lime - Cherty	3505	3545	
Lime	3545	3550	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

*Harold Rex Martin*

Subscribed and sworn to before me this 18th day of March, 1968.

*Betty M. Gmeloup*  
 Notary Public

My Commission Expires: