

22-16-17W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRONTIER OIL CO.
Farm- Stegman "A" No. 1

SEC. 22 T. 16 R.17W
SW NE SE

Total Depth. 3744'
Comm. 9-11-62 Comp. 9-22-62
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 12-15-62

County Rush
KANSAS



8 5/8" CASING:
209' cem w/130 sx.

Elevation. 2006' DF

Production. DRY

Figures Indicate Bottom of Formations.

soil & clay	30
rock	37
shale & rock	210
shale	312
sand	335
clay	392
sand	435
clay	450
sand	478
shale	515
sand	825
sand & shale	1135
anhydrite	1345
shale & shells	1493
salt & shale	1690
shale	1760
shale w/lime	2815
shale & shells	2829
lime & shale	3043
lime	3249
shale	3252
lime & shale	3300
lime	3578
conglomerate	3595
Arbuckle	3721
sand	3737
quartz	3744 RTD
Total Depth	
TOPS:	
Anhydrite	1135
Topeka	3019
Heebner	3248
Lansing-Kansas City	3300
Base of Kansas City	3523
Conglomerate	3540
Arbuckle	3595
Reagen	3712
Quartz	3730