


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRONTIER OIL COMPANY
Farm- Pfeifer "A" No. 1

SEC. 6 T. 16 R. 17W
C SE NW

Total Depth. 3509'
Comm. 11-21-62 Comp. 12-2-62
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 2-2-63

County Rush
KANSAS



Elevation. 1921' DE

CASING:
13" 61.44' cem w/50 sx.
8 5/8" 1066' cem w/450 sx.

Production. DRY

Figures Indicate Bottom of Formations.

surface soil	20
sand	30
shale & lime shells	200
red bed & shale	280
red bed & shells	475
sand	705
red bed & shale	1057
anhydrite	1100
shale & shells	1760
lime & shale	2365
shale & shells	2750
shale & lime	2990
lime	3080
lime & shale	3212
lime	3396
lime & chert	3478
lime	3509 RTD
Total Depth	

TOPS:
Anhydrite 1057
Topeka 2930
Heebner 3160
Toronto 3179
Lansing Kansas City 3211
Base Kansas City 3440
Cherty Conglomerate 3462
Weathered Arbuckle 3476
Arbuckle 3487