

State Kansas County Barton

Company G-M-R Oil Co. Well No. 1

Farm Warner

Survey 3207

Block No. 30 Sec. 30 Twp. 19 S Range 13 W

Co-Ord. 3409 Elev. 1868 K.B.

NW NW SW


Amerada - D.H.M.

Thos. H. Allan - D.H.M.

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	Spud.
		3-13-52
3-14	220	Drlg. 8 5/8" @ 786' w/325 sx.
	775	Anhydrite. WOC
3-17	1506	Drlg.
3-18	1865	"
3-19	2162	"
3-20	2565	"
3-21	2790	"
3-22	2990	"
3-23	3140	"

712 325

Date	Depth	Description
3-24	3268	Drlg.
3-25	3088	Heebner
3-26	3185	Brown Lime (-1318)
3-26	3198	Lansing (-1331)
	3202-06	Brk. Vug. Por. Sptd. Lt. Sat.
D.S.T.	3202-26	Open 1 1/4 hrs. 30' slight O&GCM. 90# BHP
3-25	3311	Drlg.
3-26	3314-28	D.S.T. Open 1/2 hrs. Strong blow throughout. Rec. 60' O&GCM. 840# BHP. Inc. as they came out.
	3328	Drlg. ahead
3-27	3452	Congl.
D.S.T.	3338-46	Open 45" Rec. 120' Sl. O&GCM. 840# BHP
	3460	Drlg.
3-28	3483	Arbuckle (-1616)
	3489	T.D. 4 1/2" @ 3485. Arb. very dense dol. with a very lt. stain in the bottom 2 ft.
T.D.	3504	dd - dp. made 4' & started getting around 250,000 cft. gas. Drld. to 3504 and last 1 1/2 ft. had fair staining and



