

State Kansas County Barton

Company G-M-R Oil Company Well No. 1


Farm Steckel Est. "A"

Survey _____

Block No. _____ Sec. 11 Twp. 20 Range 12W

Co-Ord. _____ Elev. 1801 KB

SE SE SE



GMR = 50%
Granberry - Marache - 50%

Amo Rig

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		MIRT 9-29-51
		Spud. 9-29-51
	172'	Set 8 5/8 w/130 sx.
	566	Anhydrite
10-1	1521	Drlg.
10-2	2000	Drlg.
	2971	Heebner
	3094	Brown imax Lansing
	3112	Lansing
10-5	3113-17	Stain-odor

Date	Depth	Description
	3125-28	Stain-odor
	3133-36	" "
10-5	3140	Drlg.
D.S.T.	3140-85	Open 45" rec. 25 ft. muddy water - 150# BHP
10-6	3200	Drlg.
10-7	3347	Arbuckle
	<u>3353</u>	R.T.D.
	3347-53	Fair por. f-mxln. dol. - good saturation
		5 1/2 @ 3349
10-13	D.P. Sub 10 GPH. Acidized open hole	
	3347-53	w/1000 gal ¹¹⁷⁵⁰ 1/2 BOPH SW
10-14	D.D. 3358. Sub w/20% chert. Acidized open hole from	
	3347-58	w/2000 gal 2 " "
	3347-58	3000 gal 3 " "
10-16	Sub 4 Bophs / 6 hrs	
	2 1/2 Bophs / 5 hrs	
10-17	R & D. Pumping 50 BPP -	
2-19-52	3358	R.D. Pulled Rods & tbg. Dropped to 5 Bophs
		Sub 2 Bophs.
2-20	3362	D.D. 1500 ft. Sub 4 Bophs
		R & D.