

11-16-17u


KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY FRONTIER OIL  
FARM Holzmeister "B" NO. 1

SEC. 7 T. 16 R. 17W  
LOC. SE SE NE

TOTAL DEPTH 3575  
COMM. 3-1-67 COMP. 3-11-67  
SHOT OR TREATED  
CONTRACTOR Red Tiger Drlg.  
ISSUED 4-8-67

COUNTY Rush



CASING

20	10	
15	8	5/8" @ 1125' w/500 SX
12	6	
13	* 4 1/2"	@ 3570' w/250 SX

ELEVATION 1996' KB

PRODUCTION 1' GAU 16,  
800 MCFGPD / LANS 3429  
37

FIGURES INDICATE BOTTOM OF FORMATIONS

FORMATION	FROM	TO	REMARKS
Post Rock	0	58	
Shale & Shells	58	530	
Sand	530	750	
Shale & Red Bed	750	1114	
Anhydrite	1114	1154	
Shale, Shells & Red Bed	1154	1520	
Shale	1520	1810	
Shale & Lime	1810	3190	
Lime	3190	3575	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

*George A. Angle*  
George A. Angle

Subscribed and sworn to before me this 20th day of March, 1967.

Anhydrite (Drillers)	1114	( +882)
Topeka	2991	( -995)
Heebner	3221	(-1225)
Lansing-Kansas City	3273	(-1277)
Base of Kansas City	3500	(-1504)
Cherty Conglomerate	3525	(-1529)
Sand	3568	(-1572)
Rotary Total Depth	3575	(-1579)
4 1/2" Pipe At	3570	(-1574)