

WELL RECORD

36-28-16E

API # 15-205-24,600

Well No KCAF 8 Farm Folger

Producer Kelt Oil & Gas Inc. (Oper. # 1469)

Location 3135'N SL, 3795'W EL, SW*SE-1W

Sec. 36

Twp. 28 S

Rg. 16 E

Elevation

State KANSAS

County Wilson

Kind (Oil, Gas, Water, Dry Hole) Oil

Contractor Way Drilling Co.

Producing formation

Top

Bottom

Shot with

qts.

from

to

Packer Set at

Kind

Size

Liner

from

to

Perforated from

to

LOG

Thick-ness	Strata	Depth	Thick-ness	Strata	Depth
2	Soil	2	11	Shale gy sdy	621
16	Clay-yellow	18	23	Lime (20')	644
3	Shale/sd	27	6	Slate shl dk	650
3	Lime/shl sd bks	32	9	Lime (5')	659
70	Sand gy/shl bks	102	3	Slate/trace coal	1662
20	Shale gy/sd stks	122	8	Lime br	670
16	Sand gy/shl	138	12	Sand 00/show -	
10	Shale gy dk sdy	148		top 3'	682
2	Lime brown	150	5	Sand dk/odor NB	687
4	Shale gy/lm stks	154	70	Shale dk gy sdy	757
80	Lime br wt gy	234	12	Sand Bl Brvlo NB	769
34	Sand gy/shl	268	14	Sand Br/O dor VLB-	
4	Shale gy TCT	272		/carbon laminations	783
24	Lime	296	6	Sand/shl VLO	789
6	Shale dk/slate	302	9	Sand br rainbow	
48	Lime	350		- LB in streaks	798
40	Shale slate dk	390	7	Sand wt VLO	805
11	Sand gy/shl	401	15	Sand br LB-	
4	Shale gy sdy	405		- coarse	820
3	Shale dk slate	416	7	Sand Piney odor-	
3	Lime/shl sd	419		- NB coarse	827
11	Shale G/sd lm stks	430	8	Shale gy	835
7	Lime	437	8	Sand gy wt no od	843
5	Shale gy dk	444	13	Shale gy sdy	856
2	Lime/shl bks	455	18	Shale dk	874
2	Shale gy dk	457	1	Coal	875
12	Sand gy/lm stks	469	16	Shale (RA 889-91)	891
24	Shale G dk sdy	493	12	Shale dk	913
31	Sand N.O (Weiser)	524	12	Shale gy/sd	925
27	Shale gy dk sdy	551	3	Sand/shl no od	928
4	Lime brown	555	31	Shale gy sdy	959
3	Shale CBT	558	57	Sand dk/shl lamina-	
24	Lime br (40')	582		- top Piney O top	1016
11	Slate shl dk	593			
10	Shale gy	603			
7	Sand G/00 (Peru)	610			

Total Depth 1016'

Cement surface 5 sacks

Casing 6 5/8" at 20'

Casing 2 1/2" at 845'

Casing at

Cement The 2 1/2" to the surface

Tubing

Seating nipple @ 752'

Additional Information

Well was almost devoid of coal

Date Completed 8/25/87 -- 8/28/87

O. K.

Superintendent