

3-46-19W


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **RAINS & WILLIAMSON & RAYMOND OIL**
 FARM **Seeyle "A"** NO. **1**

SEC. **3** T. **16** N. **19W**
 LOC. **NW NE NE**

TOTAL DEPTH **3602'**
 COMM. **10-14-66** COMP. **10-24-66**
 SHOT OR TREATED
 CONTRACTOR **Rains & Williamson**
 ISSUED **5-20-67**

COUNTY **Rush**



CASING

20	10	
15	8 5/8"	1229' cem w/ 475 sx
12	6	
13	5 1/2"	3601' cem w/ 125 sx

ELEVATION **2017' KB**

PRODUCTION **22 BOPD PLUS 927 W**
Reagan 3601-02 **Grave 39**

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay & post rock	105
& shale	641
shale	869
sand	1047
shale	1202
shale & red bed	1245
anhydrite	1515
shale	2035
shale & shells	2217
lime & shale	2615
lime	2855
shale w/ lime strks	2963
shale & lime	3155
lime & shale	3257
lime	3261
shale	3602 RTD
lime	
Total Depth	

TOPS: SCOUT

Anhydrite (smp)	1203
Base Anhydrite (smp)	1245
Topeka (smp)	2963
Heebner	3254
Toronto	3274
Lansing	3300
Base Kansas City	3546
Sandy Conglomerate	3590
Reagan	3599